

IN THE UNITED STATES PATENT AND TRADEMARK OFFICE

In re Application

PATENT APPLICATION

Inventor(s): Jonathan Foote, Les Nelson
John J. Doherty

SC/Serial No.: Unknown


Filed: Herewith

Title: **SYSTEM FOR CONTROLLING VIDEO
AND MOTION PICTURE CAMERAS**

**CERTIFICATE OF MAILING BY "EXPRESS MAIL"
UNDER 37 C.F.R. § 1.10**

"Express Mail" mailing label number: EL328184143US
Date of Mailing: September 7, 1999

I hereby certify that this correspondence is being deposited with the United States Postal Service, utilizing the "Express Mail Post Office to Addressee" service addressed to **Box PATENT APPLICATION, Assistant Commissioner for Patents, Washington, D.C. 20231** and mailed on the above Date of Mailing with the above "Express Mail" mailing label number.


John W. Carpenter, Reg. No. 39,129
Signature Date: September 7, 1999

APPLICATION TRANSMITTAL LETTER

Box PATENT APPLICATION
Assistant Commissioner for Patents
Washington, D.C. 20231

Sir:

Transmitted herewith for filing is the patent application identified as follows:

Inventors: Jonathan Foote, Les Nelson, John J. Doherty

Title: **SYSTEM FOR CONTROLLING VIDEO AND MOTION PICTURE
CAMERAS**

No. of pages in Specification: 39 (plus a title page); No. of Claims: 20.

No. of Sheets of Drawings: 14; Formal: , Informal: ✓.

Also enclosed are:

- ☐ Executed Declarations.
- ☐ Joint to Corporate Assignments and a Recordation Form Cover Sheet.
- ☐ A certified copy of a priority application.
- ☐ An executed Power of Attorney.
- ☐ A Verified Statement to establish small entity status.
- ☐ An Information Disclosure Statement under 37 C.F.R. §1.56.

The filing fee pursuant to 37 C.F.R. §1.16 is determined as follows:

No. Filed	No. Extra		Rate Small Entity/ Other Than Small Entity		
Basic Fee			\$380.00		
			\$760.00	=	\$760.00
Total Claims <u>20</u> - 20 = <u>0</u> *			\$ 9.00		
			\$ 18.00	=	\$0
Independent Claims <u>3</u> - 3 = <u>0</u> *			\$ 39.00		
			\$ 78.00	=	\$0
First Presentation of Multiple Dependent Claim(s) <u> </u>			\$130.00		
			\$260.00	=	\$0
			Total	=	\$760.00

*If the difference is less than zero, enter "0".

- ☐ Please charge Deposit Account No. 06-1325 in the amount of \$_____. A duplicate copy of this authorization is enclosed.
- ☒ A check in the amount of \$760.00 to cover the filing fee (\$760.00), and Assignment recording fee (\$40.00), if applicable, is enclosed.

☒ The Commissioner is hereby authorized to charge underpayment of any additional fees (including those listed below) or credit any overpayment associated with this communication to Deposit Account No. 06-1325. A duplicate copy of this authorization is enclosed.

☒ Any additional filing fees under 37 C.F.R. §1.16.

☒ Any patent application processing fees under 37 C.F.R. §1.17.

This application is filed pursuant to 37 C.F.R. §1.53 in the name of the above-identified Inventor(s).


Please direct all correspondence concerning the above-identified application to the following address:

Martin C. Fliesler, Esq.
FLIESLER, DUBB, MEYER & LOVEJOY LLP
Four Embarcadero Center, Suite 400
San Francisco, California 94111-4156
Telephone: (415) 362-3800

Respectfully submitted,

Date: Sept 9, 1999

By:


John W. Carpenter
Reg. No. 39,129

FLIESLER, DUBB, MEYER & LOVEJOY LLP
Four Embarcadero Center, Suite 400
San Francisco, California 94111-4156
Telephone: (415) 362-3800

UNITED STATES PATENT APPLICATION FOR
SYSTEM FOR CONTROLLING VIDEO AND
MOTION PICTURE CAMERAS


Inventors:

Jonathan Foote
Les Nelson
John J. Doherty

CERTIFICATE OF MAILING BY "EXPRESS MAIL"
UNDER 37 C.F.R. §1.10

"Express Mail" mailing label number: EL328184143US
Date of Mailing: September 7, 1999

I hereby certify that this correspondence is being deposited with the United States Postal Service, utilizing the "Express Mail Post Office to Addressee" service addressed to Box PATENT APPLICATION, Assistant Commissioner for Patents, Washington, DC 20231 and mailed on the above Date of Mailing with the above "Express Mail" mailing label number.



John W. Carpenter, Reg. No. 39,129
Signature Date: September 7, 1999

**SYSTEM FOR CONTROLLING VIDEO AND
MOTION PICTURE CAMERAS**

5

Inventors:

Jonathan Foote
Les Nelson
John J. Doherty

10

COPYRIGHT NOTICE

15

A portion of the disclosure of this patent document contains material which is subject to copyright protection. The copyright owner has no objection to the facsimile reproduction by anyone of the patent document or the patent disclosure, as it appears in the Patent and Trademark Office patent file or records, but otherwise reserves all copyright rights whatsoever.

20

25

BACKGROUND OF THE INVENTION

Field of Invention

30

35

This invention relates to a method and apparatus for control of one or more cameras, including motion picture cameras. The invention is also related to the control of a video camera array. The invention is more particularly related to controlling parameters of a shot of a still or video camera, particularly a pan angle and zoom of the camera being controlled. The invention is also related to interfaces for implementing control of the above and other camera parameters, including pen-based, illumination, and gesture based control interfaces.

Discussion of Background

Video cameras with controllable pan/zoom are commercially available. For example, SONY EVI-D30 has a range of zoom, tilt and pan that is controllable.

5 Deep Sea Power & Light also produces a camera (the Pan/Tilt/Zoom 2001) having controllable pan tilt and zoom (specifically designed for underwater operation). However, such systems are constrained by the limitations of the mechanical systems that orient them.

10 Current interfaces to movable and cameras are not particularly intuitive, and typically consist of contact switches that move the camera up/down, left/right, and control a degree of zooming. Often, users must "pre-program various functions". For
15 example, the SONY EVI-D30 requires a user to "pre-define" a subject for tracking, or alternatively to control the camera via an RS-232 interface.

Typically, motion of a movable camera is at one slow speed, to avoid overshoot, even if the control
20 motors are capable of variable speeds. Even professional systems have only a joystick, which limits the interface from instantaneously panning to a new destination even if the camera control hardware supports it. For example, the DEEPSEA Power & Light
25 Pan/Tilt/Zoom 2001 requires switching of control lines

to either 12VDC or 12Vret for camera control, and has a joystick control option.

A particular advantage of virtual cameras is that they can be panned/zoomed virtually instantaneously, with none of the speed limitations due to moving a physical camera and/or lens. For example, Foote et al., U.S. Patent No. __, __, __, Serial No. 09/370,406, Attorney Docket No. FXPL1003USMCF/JWC filed August 09, 1999, incorporated herein by reference, in its entirety, discloses several embodiments of virtual cameras constructed from both fixed and movable cameras and camera arrays.

SUMMARY OF THE INVENTION

The present inventors have realized that automatic control of cameras, including camera arrays, can have many large benefits. For example if the target destination is known in advance, then the camera speed can be smoothly increased and decreased thus allowing for both a smoother and more rapid camera pan or zoom compared with a conventional camera. More importantly, appropriate interfaces can reduce a cognitive load of controlling cameras, making it easy for even inexperienced users to produce quality video.

The present invention includes a direct manipulation graphical user interface. A pen or other pointing device (e.g. a mouse, trackball, etc.) provides an interface for camera control or video
5 production. A representation of the scene is used as an analog (overview) of the area to be captured on video. Icons graphically indicate camera location(s) or other parameters. Pen gestures indicate which areas of the scene are to be viewed with which video cameras,
10 and are translated into commands that control the cameras.

The scene representation can be a real image, a moving image such as a video panorama, or a pictorial, graphic, or iconic representation of the scene. A
15 gesture recognition device may also be utilized to capture gestures which are then interpreted and used to control camera pan, tilt, zoom as well as other attributes of the camera(s) (e.g., focus or color balance).

20 The present invention includes physical direct manipulation using tangible control objects. Physical "window frame" objects may be placed onto a surface that senses the location and kind of object being used. The frames are rectangular objects of the correct sizes

and aspect ratios for indicating the desired view and zoom.

The present invention includes an apparatus and method for camera target illumination or virtual
5 illumination. A handheld device is used to indicate where the camera view should be looking, by pointing the device at the desired area. The targeting device either illuminates the desired area with a detectable signal (e.g., IR) or the targeting device 'virtually
10 illuminates' the area of interest, identifying its location from the position and orientation of the device pointed towards it.

One goal of the present invention is to simplify the camera controls necessary for 'routine' camera use
15 in such applications as video conferencing, meeting capture, motion picture productions, or other general video or photographic production scenarios. Camera controls of the present invention involve a 'set-it, forget-it' action (e.g., gesture, manually nudging a
20 frame token, or pointing an illuminator) from any user in the meeting space. In this way, a person present in a meeting will be not be continuously absorbed by the camera control, and, hence, will have a better chance in being able to participate in the discussion.

The present invention is embodied as method of presenting a user interface for control of at least one camera, comprising the steps of, displaying a wide angle view of scene, displaying a drag and drop icon
5 associated with a camera, and directing said camera toward a location in said scene corresponding to a position on said wide angle view that said icon is dragged and dropped.

The present invention also includes a method of
10 presenting a user interface for control of at least one camera, comprising the steps of, displaying a wide angle view of a scene on a pen based device, recognizing an input drawn on said pen based device, directing a camera toward a location in said scene
15 corresponding to a position on said wide angle view that said input is drawn, and displaying a view associated with the input drawn. The pen based devices can be a tablet (hand-held or notebook style display with a pen input mechanism), or a full desktop or other
20 computing and display mechanism with a pen input mechanism.

The present invention may be embodied in a device for directing a camera, comprising, a control display panel, having, a detection mechanism configured to

detect an object placed on said control display panel,
and a camera control device configured to direct at
least one camera toward a scene at an angle
corresponding to a location said object was placed on
5 said control display panel.

Each method and embodiment of the present
invention provides a new way to control cameras
associated with video and/or still photographs.

10

BRIEF DESCRIPTION OF THE DRAWINGS

A more complete appreciation of the invention and
many of the attendant advantages thereof will be
readily obtained as the same becomes better understood
by reference to the following detailed description when
15 considered in connection with the accompanying
drawings, wherein:

Fig. 1 is a flow diagram of image and control data
according to one embodiment of the present invention;

Fig. 2 is a flow chart illustrating steps for
20 identifying and performing camera commands and
operations;

Fig. 3 is an example of an icon based user
interface for directing camera views;

Fig. 4A is an example of a pen based user interface for directing camera views;

Fig. 4B is an example of graphical selection of camera views from a panoramic view, and assignment of
5 cameras to selected views;

Fig. 5A is a graphical illustration of one embodiment of a view control mechanism utilizing physical tokens and a touch sensitive (tangible) control surface;

10 Fig. 5B is an embodiment of a tangible control surface and control tokens;

Fig. 5C is a block diagram of a view display apparatus according to one embodiment of the present invention;

15 Fig. 6A is a diagram illustrating a spatial user interface for implementing a view control mechanism;

Fig. 6B is an illustration of a set of physical tokens;

Fig 6C is an illustration of a re-sizable physical
20 token according to the present invention;

Fig. 7 is an illustration of steps for identifying and producing a view based on view control mechanism and a tangible token;

Fig. 8A is block diagram of one embodiment of a view control mechanism having a sensing device for recognizing illumination areas for directing camera operations;

5 Fig. 8B is a block diagram of one embodiment of a view control mechanism having a detector for detecting illuminations in frames captured by a camera to be controlled by said illuminations; and

10 Fig. 9 is an example of an Internet based embodiment of the present invention.

DESCRIPTION OF THE PREFERRED EMBODIMENTS

Referring now to the drawings, wherein like reference numerals designate identical or corresponding parts, and more particularly to Fig. 1 thereof, there is illustrated a flow of image and control data through a system that is shared by several embodiments of the present invention. The system includes a camera 100. The camera 100 is illustrated as a camera array, and
15 may also be embodied as any camera or image capture device, such as a simple digital or analog camera, a camera array, wide angle camera, and a steerable camera, for example.
20

The camera 100 provides a wide-angle camera view of a scene to support an electronic clipping process. A camera data stream 110 is split and directed simultaneously to a clipping control component 120
5 (also referred to as the camera view control 120) and a display view 130 (e.g., videoconference image, meeting capture recording, display device, etc).

In one embodiment, simple user actions are captured by the camera view control 120 and used to
10 determine a location of the user's area of interest. Processes performed by the camera view control 120 are illustrated in the flow diagram of Fig. 2. A wide angle view from camera 100 is retrieved at step 200.

At step 210, the wide angle view is scanned to
15 identify gestures of individuals captured in the wide angle view. Alternatively, camera view control 120 scans the wide angle view for illuminations (from an illumination device as described below) or receives commands from an input mechanism or other device. In
20 yet another alternative, user actions associated with the camera view control 120 are recognized (a tapping or side to side motion of a token (see Fig. 5A), indicating turn the view on or off, for example).

In the case of gestures, the wide angle image is scanned for gestures (e.g., pointing (laser devices, for example), or other framing motions made by participants captures in the wide angle view) indicating an area of interest or other specific camera command. In the case of illuminations, the illuminations are recognized via any of line tracing, line recognition or other image processing procedures performed on the wide angle view. In the case of user actions, a code associated with the action or a program flow identifies the action.

At step 220, the gestures, illuminations, and/or user actions are interpreted to identify an action or a command to be implemented. For example, the camera control view may identify an "arms crossed" command from an individual in the wide angle view indicating the camera is to be turned off. At step 230, the identified action or command is performed or sent to a device to be performed (in the above example, the camera is turned off, or a command is sent to the camera to turn it off).

A user action for setting an area of interest could be either a gesture (e.g., pointing) or other mechanism (e.g., illumination mechanism, or drag and

drop icon) for specifying a location of an area of interest. The position of the area of interest is utilized by the camera view control 120 to determine a region to be clipped (disregarded) in the display view, in order to leave a frame in the display view encompassing the area of interest.

Clipping commands 140 are sent to the display processor in order to perform the clipping operation of the wide-angle view needed to produce the isolated or display view 130. A display processor sizes the image to the aspect ratio required of a display device that displays the display view 130 (zooming the clipped region as needed, maintaining a fixed aspect ratio).

Optionally, at least some of the clipping commands 140 may be formatted as camera control commands 150 and fed back to the camera 100. The camera control commands 150 include any of steering commands (e.g., pan or zoom commands), clipping commands, and advanced processing commands (e.g., image processing of areas of interest). Alternatively, instead of clipping a wide-angle view, a steerable camera can be directed to the appropriate pan/zoom coordinates.

Fig. 3 shows an example of one embodiment of a two-camera control interface, and a pen or pointer

based graphical user interface, using icons, which can be extended to any of one camera, an arbitrary number of cameras, or any number of virtual views from either of a single camera, plural cameras, or a camera array.

5 Each field of view of a camera A and a camera B is shown iconically, via control icons 310 and 320 respectively, on a background image 300 of a conference room scene.

The cameras are controlled by interacting with its

10 respective control icon. Each control icon includes handles (e.g., camera A control icon 310 including outer handle 312 and center handle 314, and camera B control icon 320 including outer handle 322 and center handle 314). Moving the center handle of an icon moves

15 the corresponding camera's view. Moving an outer icon handle changes the cameras zoom ratio; moving the outer handles closer to the center zooms in while the camera's field of view can be expanded by enlarging an area delineated by the handles. Other handles or icons

20 (a sliding control bar, for example) can apply or cue different effects (e.g., a sliding control bar for adjusting brightness or contrast). Thumbnail images indicating the actual camera view can be incorporated in the control icon.

The background image 300 (a wide angle or panoramic view) can reflect the actual scene being shot or any graphic representation, including iconic or schematic ones such as floor plans or artists' renderings. Multiple places, scenes, or views can be used; for example two room scenes can be placed next to each other regardless of the actual room locations. In one embodiment, a "background" panorama of the scene is composed by excluding occluding objects using a fixed wide-angle camera. The objects may be excluded by any method, including median-filtering each pixel value over a predetermined time, so that non-background (occluding) objects are ignored. If an object is in place longer than the predetermined time extent, it becomes part of the background. Alternatively, the wide-angle camera is used in a special mode to capture the background while the operator ensures that no foreground objects or people are in the scene.

In yet another mobile camera images are used to "repaint" the panoramic scene (background image 300). As a camera image is moved over the scene, it would leave behind its most recent view of that scene area.

Fig. 4A shows an alternative interface suitable for a pen-based device. Here, the user circles a

desired camera location on the background image 300 with a scribbling motion (e.g., scribbling motions 400, 410, and 420). The system (camera view control 120, for example) determines the width and height of the scribble and fits a rectangle (e.g., rectangles 405, 415, and 425) with the proper camera aspect ratio (Alternative configurations allow displays with altered aspect ratios, or part screen displays).

Fig. 4B illustrates an example of a graphical selection of camera views from a panoramic view 430, and assignment of cameras to selected views. A panoramic view (panorama) 430 is displayed by a camera control application 435. A user selects a view from the panorama by pointing and dragging an expandable frame on the desired view location of the panoramic view 430. In the case of a virtual camera, the view is composed from a wide angle shot or composite image of a camera array and displayed on a display device (550, for example, see Fig. 5), and may also be shown on the camera control application 435 as a reference view 440, for reference by the user. Each reference view would include standard dialog icon, expand, and full-size control buttons (e.g., control buttons 450).

In the case of fixed cameras, the camera control application may select an appropriate camera to retrieve the selected view, or the user may assign a camera. In one embodiment, the camera control application would be configured to automatically recognize cameras providing video to the video stream and provide an icon for each. A user would then match a camera with a view by drawing a line (e.g., line 445) between a camera icon and a selected view. Alternatively, cameras could be recognized or added via a separate control function (e.g., add view button 435) or pull down menu, which would provide or query for any addition set-up information needed.

Although Fig. 4B illustrates a pointing device (e.g., hand 455), the illustrated processes may be performed by any user interface, including pen based systems as discussed above. Possible user/device interactions for indicating the processes to be performed (e.g., moving the camera view (pan/tilt/zoom) and changing camera attributes), may be performed in many different manners. For example:

1. To move camera view:
 - a. Click or indicate desired region
 - b. Draw "rubber band" line from camera icon to desired region
 - c. Circle indicated region

- d. Click on relative position control
- e. Click on absolute position control
- f. Grab scene and move "under" camera
- 5 g. Grab camera icon and move to desired position
- 2. To change zoom attributes:
 - a. Draw larger circle, circle direction (cw/ccw), or spiral outwards
 - 10 b. Draw smaller circle, circle direction, or spiral inwards
 - c. Grab zoom control/scroll bar
 - d. Grab and move edge of camera indicator box or handle brackets
- 3. To change Focus:
 - 15 a. "Scribble" to change or auto focus
 - b. Grab focus control/scroll bar
- 4. To change or switch camera:
 - a. Gesture "X" to turn off camera
 - 20 b. Camera position indicator replaces another camera: switch to new camera
 - c. Click on camera icon

A paper-based version of pen-based camera control may be realized using a printed image of the panoramic view or scene. Selection of points of interest on the paper may be determined by using paper encoded with Xerox DataGlyphs (i.e., data carpet) (see http://www.seyboldseminars.com/seybold_report/reports/D0905001.HTM, for example). Alternatively, a stylus tablet (e.g., Wacom <http://www.wacom.com>) may be used for the pen input. In yet another alternative, a

printout of the panoramic view on plain paper may be drawn on and scanned into the camera view control 120.

Another embodiment of the present invention, including a tangible camera control interface, is illustrated in Fig. 5A. A view control mechanism 500 includes a tangible control surface 510, which displays a panoramic or other representation of a scene viewed by at least one camera 540 (shown as a camera array) according to the present invention.

Physical "window frame" objects 520 and 530 (frame objects, also called tokens) are used to represent camera views. The frame objects 520 and 530 are placed onto the tangible control surface 510 at fields of interest of the scene. The tangible control surface 510 includes a detection mechanism for detecting presence of frame objects (e.g., a touch sensitive display). In one embodiment, a touch sensitive screen determines the size and shape of the token via an area touched on the screen. In another embodiment, a bar code or other identifying marks (e.g., an electronic tag) are read via an input mechanism (e.g. touch sensitivity, scanning, electrical field detection).

In one embodiment, the frame objects are rectangular and are precut to a correct size, allowing

a detection of the physical attributes of the frame objects to allow the camera view control 120 to provide corresponding camera control, including detection for clipping the video stream and showing the clipped view
5 on a full screen display at a proper aspect ratio. In another embodiment, the tokens are virtual and re-sizable to maintain a correct aspect ratio.

To activate the control, the user places the frame on the panoramic view of the tangible control surface
10 510. The panoramic view is clipped and displayed at a user output 550, or provided to a recording device (not shown), or a projection device (not shown). In alternative embodiments, the clipping process may be performed at the view control mechanism 500 and the
15 clipped images sent to user output 550, or the panoramic view and clipping commands are sent to user output 550 where the clipping process is performed before sending the clipped image to the display device.

Picking up a frame object removes the clipped view
20 associated with that frame object. Dragging a frame object pans the view. Multiple frames may be used to quickly select between multiple views by touching the frame of interest. Lastly, the tangibility of the frames offers a unique capability: the user may hold a

frame over the display without dropping it to "cue up"
a view without invoking the electronic control
function.

In one embodiment, the flow of video data through
5 the tangible interface is shown in Fig. 5B. Frame
objects of preset size (560, for example) indicate the
clip regions. A camera data stream 545 is split and
directed simultaneously to the tangible control surface
510 and a display application 555 (e.g.,
10 videoconference image, meeting capture recording,
etc.). Each token location is used to determine the
clipping region needed for the display view. The
clipping commands are sent to a display processor 570
(a part of the display application 555, for example,
15 see Fig. 5C) in order to perform the clipping operation
of the wide-angle view needed to produce the clipped or
isolated view 565.

The display processor 570 sizes the image to the
aspect ratio required of the display application 555.
20 Optionally, the clipping commands may be fed back to
the camera for advanced processing (e.g., image
processing of areas of interest).

An example enlargement of the tangible control
surface 510 is shown in Fig. 6. The tangible control

surface 510 has the following features for supporting wide-angle view clipping:

Physical see-through tokens

Physical see-through frame tokens 610 and 620
5 select clipping regions of a wide-angle view 600. The physical constraints of the frame tokens help simplify the control interaction between the user and the tangible control interface. Again, the user may look through the tokens to see what will be displayed before
10 invoking the clipping action by dropping the token. The material the tokens are constructed from may be of a transparent or light conducting material such that parts of the scene covered by the token material may be viewed without lifting the token.

15 Preset Token sizing

The size of the frame may be preset to the correct aspect ratio needed, freeing the user from having to make such adjustments. If one preset size is not quite right for a particular view, a collection of several
20 larger or smaller tokens (630, Fig. 6B, for example) could be kept handy. However, an expandable/collapsible frame (640, Fig. 6C, for example) capable of changing in size but preserving a correct aspect ratio may also be used. The system

could also select the appropriate clipping region that covers the frame token (approximating a size to clip, while automatically preserving the correct aspect ratio of any object placed on the tangible control surface).

5 In another embodiment, an adjustable frame size is identified by two tokens that mark, for example, an upper left and lower right corner of a frame to be captured. In yet another embodiment, a virtual token may be drawn on the control surface (via Etch-a-Sketch
10 type controls, for example), and activated via software controls (automatically, or via buttons, selection boxes, pull down menus, etc).

 Tokens may also be pre-defined and preset at a specific location on the control surface. In cases,
15 such as lecture halls or conference rooms, presetting a token, or a frame of the wide angle view to encompass a speakers podium, white board other visual aids would allow for fast switching between the preset views. The views may be activated by touching an area of the
20 control surface (510, for example), or via software controls (automatically activated based on motion, for example, or via operator controls such as buttons or pull-down menus). The tokens themselves may be preset on the control surface, virtually drawn on the control

surface, or need not even be present (perhaps shown on a startup display of the control surface, or temporarily displayed if requested by an operator).

5 Token activation

 Tokens may be active or inactive (e.g., cued for next display). For example a button indicator (650, for example) may be affixed to a token or a gesture sequence with the frame (e.g., small side-to-side
10 motion) may be recognized by a location underlying the token.

Token Placement

 Active and inactive viewing regions may be moved as needed. Dragging a token pans the view. Picking up
15 and dropping a token swaps views. An active/inactive indication may be used to keep a spurious view of the wide-angle camera shot from intervening during this kind of camera switching.

 For example, a user can pick up, drop, and
20 activate a token to 'change' views. In addition, a user might use two tokens and swap between views by alternately activating one or the other.

The isolated view display 660 shows the active region selected by the tokens by performing a clipping operation on the wide field view 600. Communication of the clipping data may be performed by a network communication (e.g., remote procedure call, socket communication, remote method invocation) or any interprocess communication mechanism (e.g., shared data, code segments, etc.) for programs running on the same computer.

10 Sensing the tangible control token involves detecting the token identity, the token location in the tangible control surface reference frame, and detecting the active/inactive frame state. The detection of identity, location, and event may be performed as
15 provided by Nelson et al., U.S. Patent Application Serial No. 09/152,677, Attorney Docket No. 100931, entitled "Systems and Method for Controlling a Presentation Using Physical Objects," filed September 14, 1998, which is incorporated herein by reference, in its entirety.

20 Described with reference to Fig. 7, a tangible control token 700 is placed on a tangible control surface 710 displaying a wide angle view 600 at location 715. The touch sensitive screen detects 720 the presence of the token 700 and determines whether or

not the token is active (detecting additional pressure, or a sequence of events, taps, for example). The token is identified 730 based on a pattern or other communication mechanism between the token and touch sensitive screen. And finally, a location of the token is determined 740, which includes any one of a center position (x,y), a position and a radius or other geometric properties (length & width, for example). Each of the position determined, ID of the token, and whether the token is active or inactive is provided to a command device (730, for example) which determines clipping commands to produce a display 750.

Camera Control by Target Illumination or Virtual Illumination

As described briefly above, the present invention includes capturing and interpretation of physical gestures to control cameras configured according to the present invention. The physical gestures indicate an actual area (area of interest) to be filmed.

In one embodiment, as shown in Fig. 8A, a user uses a handheld illumination source, such as an infrared semiconductor laser 800. The user indicates a desired area 810 by pointing at the desired area 810

and illuminating it with the illumination source 800. An IR-sensitive sensor 820 (such as a CCD camera) determines a position of the illuminated area, and a command control device 830 translates the location into
5 clipping control parameters (clipping commands), so that the illuminated area is clipped from the wide-angle view. The user can either scribble the illuminated area with a beam from the laser, or, alternatively, a predetermined geometric shape
10 projected by the laser and adjusted in size by a sizing selection mechanism (e.g., up-down buttons 802 or a roller knob 804).

In another embodiment (see Fig. 8B), the camera 540 detects the laser image projected by the laser 800, the detection being included in the video stream 545
15 and sent to view control mechanism 500. An IR detector 840 detects the laser image in the video stream, which signals the command device 830 to set clipping control parameters (clipping commands) and other camera
20 controls when applicable (such as, for example, the case of camera controls being fed back to the camera 100, as discussed above, e.g. panning and zooming).

In yet another embodiment, a handheld directional device is used to indicate the desired area. Sensors

on the device that can determine spatial position and orientation (for example, the Polhemus FastTrak [http://www.polhemus.com]) can be used to specify a desired location or area by pointing at it. Given
5 absolute position and an orientation vector, the system can determine the area pointed at by finding the intersection of the orientation vector with a known distance curve, for example, a room wall or conference table edge. If range can be determined, for example
10 using an ultrasonic rangefinder (e.g., Polaroid sonar range finder [www.polaroid.com]), the 3D coordinates can be determined precisely and translated into clipping control parameters.

Fig. 9 illustrates an Internet based embodiment of
15 the present invention. A camera array 902 produces a video stream 910 that is fed into a server 920. The server 920 broadcasts (in response to a query) a panorama of scene 900 retrieved from the video stream 910, and an applet or other program for presenting and
20 selecting views from the panorama to a requesting computer, 940A for example (alternatively, the applet or other program may already be resident on the requesting computer).

The requesting computer 940A then displays the panorama and provides at least one drag and drop icon 942 for scene selection. The applet recognizes the location and size of the drag and drop icon 942 and
5 sends clipping commands identifying a requested view over the Internet to server 920. The server 920 utilizes the clipping commands to produce an image (high resolution, super-resolution, , or stereo image, for example) that is then sent back to the original
10 requesting computer 940A, now shown as 940B with an image of the requested view.

In one embodiment, the server 920 utilizes a composition mechanism 922 to compose the panorama from plural camera views of camera array 902, and a clipping
15 mechanism 924 clips the selected view from the video stream or a super-resolution composite of the images present in the video stream. The invention may be practiced across a normal modem connection via an Internet Service Provider, a cable modem, DSL, ISDN,
20 T1, T3, or any other type of Internet connection in a stand alone mode or in conjunction with another network (e.g., a satellite network, or Ethernet 930).

A specific configuration for a remote based application of the present invention would be selected

based on the availability of broadcast bandwidth and processing power available at each of the server 970, connected network (Internet in the above example, but could be embodied in any local area, wide-area, 5 satellite or other network type). As will be appreciated by those skilled in the art, any number of combinations or modifications of the Internet based embodiment and the mechanisms implementing it may be realized, consistent with the invention as described 10 herein.

Many of the embodiments of the present invention is described herein are described with reference to video or filming operations, however, as will be appreciated by those skilled in the art, the same 15 processes and procedures apply to both video and still image captures.

The present invention may be conveniently implemented using a conventional general purpose or a specialized digital computer or microprocessor 20 programmed according to the teachings of the present disclosure, as will be apparent to those skilled in the computer art.

Appropriate software coding can readily be prepared by skilled programmers based on the teachings

of the present disclosure, as will be apparent to those skilled in the software art. The invention may also be implemented by the preparation of application specific integrated circuits or by interconnecting an appropriate network of conventional component circuits, as will be readily apparent to those skilled in the art.

The present invention includes a computer program product which is a storage medium (media) having instructions stored thereon/in which can be used to control, or cause a computer to perform any of the processes of the present invention. The storage medium can include, but is not limited to, any type of disk including floppy disks, optical discs, DVD, CD-ROMs, microdrive, and magneto-optical disks, ROMs, RAMs, EPROMs, EEPROMs, DRAMs, VRAMs, flash memory devices, magnetic or optical cards, nanosystems (including molecular memory ICs), or any type of media or device suitable for storing instructions and/or data.

Stored on any one of the computer readable medium (media), the present invention includes software for controlling both the hardware of the general purpose/specialized computer or microprocessor, and for enabling the computer or microprocessor to interact

with a human user or other mechanism utilizing the results of the present invention. Such software may include, but is not limited to, device drivers, operating systems, and user applications. Ultimately,
5 such computer readable media further includes software for performing the present invention, as described above.

Included in the programming (software) of the general/specialized computer or microprocessor are
10 software modules for implementing the teachings of the present invention, including, but not limited to, identification of gestures, laser emissions, pen drawn shapes, identification of touch or pressure sensitive signals, building and/or formatting of commands to
15 control a clipping process or control functions of a camera or camera array, and the display, storage, or communication of results according to the processes of the present invention.

Obviously, numerous modifications and variations
20 of the present invention are possible in light of the above teachings. It is therefore to be understood that within the scope of the appended claims, the invention may be practiced otherwise than as specifically described herein.

WHAT IS CLAIMED AND DESIRED TO BE SECURED BY LETTERS
PATENT OF THE UNITED STATES IS:

1 1. A method of providing a user interface for
2 control of at least one camera, comprising the steps
3 of:

4 displaying a representation of a scene;

5 displaying at least one drag and drop icon
6 associated with at least one camera; and

7 directing at least one view of said at least one
8 camera toward locations in said scene corresponding to
9 positions identified on said representation by said
10 icons.

1 2. The method according to claim 1, wherein said
2 step of directing comprises the step of retrieving at
3 least one virtual view, from at least one of said
4 cameras, corresponding to said positions identified.

1 3. The method according to claim 1, wherein said
2 step of displaying comprises the steps of:

3 retrieving plural camera images; and
4 composing said representation from said plural
5 camera images.

1 4. The method according to claim 1, wherein:
2 said at least one camera is a camera array; and
3 at least one of said drag and drop icons each
4 correspond to a virtual view of said camera array.

1 5. The method according to claim 1, wherein:
2 at least one of said drag and drop icons is an
3 expandable drag and drop icon, and an amount of zoom of
4 the associated camera is controlled by a size of said
5 drag and drop icon.

1 6. The method according to claim 5, further
2 comprising the step of:
3 maintaining a proper aspect ratio during user
4 resizing of said drag and drop icon.

1 7. The method according to claim 1, wherein said
2 drag and drop icon is a frame like object indicating a
3 view of said camera.

1 8. The method according to claim 1, wherein:
2 at least one of said drag and drop icons has a
3 center portion and a handle movable with respect to
4 said center portion; and
5 said method further comprises the step of:
6 adjusting a parameter of at least one of said
7 cameras based on a position of said handle in an icon
8 associated with the cameras being adjusted.

1 9. The method according to claim 8, said
2 parameter is at least one of an amount of zoom,
3 brightness, contrast, and other effects of the
4 associated camera.

1 10. The method according to claim 1, further
2 comprising the step of:

3 panning a view of a camera associated with a
4 selected icon during a drag operation performed on the
5 selected icon.

6 11. A method of providing a user interface for
7 control of at least one camera, comprising the steps
8 of:

9 displaying a wide angle view of a scene on a pen
10 based device;

11 recognizing an input drawn on said pen based
12 device;

13 directing a camera toward a location in said scene
14 corresponding to a position on said wide angle view
15 that said input is drawn; and

16 displaying a view associated with the input drawn.

1 12. The method according to claim 11, wherein:

2 said camera comprises a camera array;

3 said step of recognizing comprises the step of
4 recognizing inputs drawn on said pen based device;

5 said step of directing comprises selecting a
6 virtual view for each of said inputs said wide angle
7 view from images; and

8 said step of displaying comprises the step of
9 displaying at least one of said virtual views.

1 13. The method according to claim 11, wherein:

2 said step of recognizing comprises the step of
3 recognizing an approximate size of said input drawn;
4 and

5 said method further comprises the step of zooming
6 said camera to an approximate view covered by the
7 approximate size of said input drawn.

1 14. The method according to claim 13, wherein:

2 said step of recognizing comprises the step of
3 recognizing an approximate size and shape of said input
4 drawn; and

5 said method further comprises the step of a view
6 covered by the approximate size of said input drawn.

1 15. A device for directing a camera, comprising:
2 a control display panel, having,
3 a detection mechanism configured to detect an
4 object placed on said control display panel; and
5 a camera control device configured to direct at
6 least one camera toward a scene at an angle
7 corresponding to a location said object was placed on
8 said control display panel.

1 16. The device according to claim 15, further
2 comprising an object for placement on said control
3 display panel.

1 17. The device according to claim 16, wherein
2 said object is at least one of a pen and a token.

1 18. The device according to claim 15, wherein
2 said control display panel is further configured to
3 display a wide angle view of said scene.

1 19. The device according to claim 15, wherein:
2 said detection mechanism is further configured to
3 detect a size and shape of objects placed on said
4 display panel; and
5 said camera control device is further configured
6 to adjust a parameter of said at least one camera based
7 on at least one of a size and shape of said objects.

1 20. The device according to claim 19, further
2 comprising a set of at least one physical token
3 configured to control functions of said camera control
4 device based on a size and shape of the tokens.

ABSTRACT

Inputs drawn on a control surface (pen based inputs) or inputs retrieved based on tokens or other objects placed on a control surface are identified and
5 a view of a camera, or a virtual view of a camera or camera array is directed toward a corresponding location in a scene based on the inputs. The inputs may be in the form of drag and drop icons. A panoramic or wide angle view of the scene is displayed on the
10 control surface as a reference for user placement of tokens, drawings, or icons. Camera icons may also be displayed for directing views of specific cameras to specific views identified by any of drag and drop icons, tokens, or other inputs drawn on the control
15 surface. In one embodiment, clipping commands, generated based on an input and wide angle view, are sent to a display device along with the wide angle view which is then clipped to a view corresponding to the input and displayed on a display device, broadcasting
20 mechanism, or provided to a recording device. The invention may be performed on all locally connected hardware and software, or in a remote configuration across a local or wide area network or based on Internet communications between any of the cameras,
25 control devices, or user interfaces.

Wide Angle Camera/ Steerable camera




FIG. 1




FIG. 2




FIG. 3




FIG. 4A




FIG 4B




FIG. 5B




FIG. 5C




FIG. 6A




FIG. 6B




FIG. 6C

660000-111660




FIG. 7




FIG. 8A




FIG. 8B

Year	1990	1991	1992	1993	1994	1995	1996	1997	1998	1999	2000	2001	2002	2003	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	2036	2037	2038	2039	2040	2041	2042	2043	2044	2045	2046	2047	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074	2075	2076	2077	2078	2079	2080	2081	2082	2083	2084	2085	2086	2087	2088	2089	2090	2091	2092	2093	2094	2095	2096	2097	2098	2099	2100
1990	1991	1992	1993	1994	1995	1996	1997	1998	1999	2000	2001	2002	2003	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	2036	2037	2038	2039	2040	2041	2042	2043	2044	2045	2046	2047	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074	2075	2076	2077	2078	2079	2080	2081	2082	2083	2084	2085	2086	2087	2088	2089	2090	2091	2092	2093	2094	2095	2096	2097	2098	2099	2100	




FIG 9.